



ATLAS of ERTMS

ATLAS of ERTMS

Worldwide Implementation 2009



Prepared in connection with
UIC ERTMS World Conference
Málaga, 31st March - 2nd April 2009





ATLAS of ERTMS

ATLAS of ERTMS

Worldwide Implementation 2009



Prepared in connection with
UIC ERTMS World Conference
Málaga, 31st March - 2nd April 2009



ISBN 978-2-7461-1630-6 (English version)

Copyright

Reproduction of this document or part of this document is authorized provided source « UIC 2009 » is mentioned.
This work is entirely protected by the French Intellectual Property Code – articles L 122-4 and L 122-5

Table of contents

Introduction	5
Algeria	8
Australia	10
Austria	12
Belgium	14
Bulgaria	16
China	18
Croatia	20
Czech Republic	22
Denmark	24
Finland	26
France	28
Germany	30
Greece	32
Hungary	34
India	36
Italy	38
Lithuania	40
Luxembourg	42
Mexico	44
Norway	46
Poland	48

Portugal	50
Romania	52
Saudi Arabia	54
Slovakia	56
Slovenia	58
Spain	60
South Korea	62
Sweden	64
Switzerland	66
Taiwan (China)	68
The Netherlands	70
Turkey	72
United Kingdom	74
Some statistics on ETCS	77
Some statistics on GSM-R	83
List of abbreviations	87
Annex: Detailed GSM-R Maps	89

Introduction

UIC Atlas of ERTMS worldwide implementation 2009 release

The International Union of Railways conducted a survey on the situation of ERTMS, with the objective of delivering this Atlas during the UIC ERTMS World Conference 2009 held between March 31st and April 2nd in Málaga – Spain. Information reported in the ATLAS is extracted from the database on ERTMS implementation managed by UIC. This database is built on official information given by Platform members with the objective of offering them an ongoing added-value service and to maintain Platform strategic position and understanding of the rail business. The ATLAS 2009 is the most comprehensive assembly of concise information available on ERTMS implementation at this point in time. The survey presents a picture of the situation, as of December 2008, of the installed ERTMS components: ETCS, (the European standardised control command system) and GSM-R, (the standardised railway radio digital communication system) in respect of the implementation programmes in many countries.

Each ETCS project has been classified within one of the four following categories (status):

- Pilot/test means the infrastructure and/or rolling-stock is being tested, but not yet in commercial service;
- Contracted status means that a contract has been awarded to a supplier to equip the infrastructure and/or rolling-stock;
- Commercial operation means the line is in revenue service with ETCS;
- Planned is a status used for potential projects for which no contract has been awarded yet; for instance, that would typically be the case for lines that are part of important corridors.

A specific colour was assigned to each ETCS level, whereas continuous lines were used to represent commercially operated lines (dotted lines for contracted or planned lines).

The above-mentioned statuses were assigned according to the national infrastructure manager or railway undertaking view point. When a country contracted both ERTMS Level 1 and Level 2 for the same section, we counted it as Level 2 in the statistics.

Similarly to the last edition, the set of concise information that is given in the form of a table is also displayed on a map for a convenient visualization. The term “section” or “route length” refers to the distance in km between the two cities connected by the project, and therefore can be single, double track or even triple track depending on the projects.

A similar approach has been adopted for rolling-stock to identify its status with regards to ERTMS. Usually, rolling-stock is classified using power supply source (Diesel, DC, AC, etc.). But given the impact of ETCS on the various types of engines, the classification below seemed more suitable.


The various acronyms stand for:

EMU: Electric Multiple Unit;
DMU: Diesel Multiple Unit;
HST: High Speed Train;
MMI: Man Machine Interface.

Type	Architecture	Comments	Example
Single Cab Unit		One MMI One such engine per train	if self-propelled: switching/shunting/ plant loco; if not self-propelled: propelling control vehicle, driving van trailer...
2-cab loco		Two MMIs One such engine per train	General purpose self-propelled locos: suited both for freight and passenger cars trailing, track inspection locos...
EMU DMU HST		Two MMIs Two such engines per train	Conventional or high speed multiple units

“New” refers to newly-bought engines with ETCS on-board equipment included, whereas “retrofitted” refers to engines initially bought without ETCS on-board, and upgraded afterwards.

Contrary to ETCS which has been deployed on specific routes, GSM-R has been deployed on a national basis. As a consequence, the status of GSM-R is given by the colour of the map, showing its different implementation phases:



All this information was kindly provided by our members and UNIFE. The data collection process was frozen on 5th December 2008. However, very late contributions have been integrated when possible.

The following pages give country-specific information, whereas the reader can refer to statistics pages for global trends overview. “Europe” should be interpreted as the European continent, not the European Union (for instance, the Swiss data is encompassed in the European one).



ATLAS of ERTMS

ATLAS of ERTMS

Worldwide Implementation 2009

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Annaba - Ramdane Djamel	96	1 and 2	Contracted	2010	-	-	-	-	-	-
El Gourzi - Bordj BouArreridj	226	1 and 2	Contracted	2010	-	-	-	-	-	-
El Khemis - Oued Sly	104	1 and 2	Contracted	2010	-	-	-	-	-	-
Total	426									

Infrastructure

Total length of Rail Network	[km]	-
Planned GSM-R		-
Network Constructed		-
Network in Commercial Operation		-

Milestones

Start of Planning	[year]	-
Start of Implementation		2006
Ready for Operation		-
End of Migration		-


GSM-R

Mobile stations

		Planned	Activated
Mobile Users Planned	[unit]	-	-
Cab Radios		-	-
Dispatchers		-	-

Additional Information

The first GSM-R contract for the line EL-Gourzi – Touggourt has been awarded in 2006. Two new contracts were awarded in 2008: Tabia – Mecheria and Bordj-BouArreridj – M'Sila.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

AUSTRALIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Penrith to Glenbrook	13,5	1	Pilot	2007	Pilot	EMU	V-set 4-car	1	Retrofitted	2007
Wentworth Falls to Katoomba	11,5	1	Pilot	2007	Pilot	EMU	V-set 4-car	1	Retrofitted	2007
Medlow Bath to Mt Victoria	15,3	1	Pilot	2007	Pilot	EMU	V-set 4-car	1	Retrofitted	2007
Total	40,3				Total			3		

Infrastructure	Total length of Rail Network	[km]	-
	Planned GSM-R		-
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	-
	Start of Implementation		2008
	Ready for Operation		-
	End of Migration		-

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	-	-
	Cab Radios		-	-
	Dispatchers		-	-

Additional Information

The first GSM-R project with an upgrade of the Victorian urban rail networks has already started.



ETCS implementation status

- Commercial operation L1
- Contracted or Planned L1
- Commercial operation L2
- Contracted or Planned L2
- Commercial operation L3
- Contracted or Planned L3

AUSTRIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Wien to Hungarian border section Hegyesschalom	67	1	Commercial operation	2006	Commercial operation	Loco	ES64U2	13	Retrofitted	2005
Total	67				Total			13		
Wien - Salzburg Wels - Passau	394	1	Contracted	2009	Planned	Loco	ES64U2	332	Retrofitted	09/15
Total	394				Planned	Loco	ES64U4	50	Retrofitted	09/15
Wien - Graz (Südbahn)	211				Planned	Single cab unit	OeBB 8633	10	Retrofitted	09/12
Salzburg - Schwarzach - Wörgl	104	1	Planned	2012	Planned	Single cab unit	OeBB 8090	67		09/14
Innsbruck - Bregenz	75	1	Planned	2013	Planned	HST	ICE-T	3	Retrofitted	09/12
Hohenau - Wien	83	1	Planned	2013	Total			462		
Wörgl - Innsbruck existing line+ new HS line	59	1	Planned	2013						
Wien - St. Pölten New HS line	65	2	Planned	2012						
Innsbruck - Brennero	54	2	Planned	2012						
Total	651	1	Planned	2013						


Infrastructure	Total length of Rail Network	[km]	5500
	Planned GSM-R		3500
	Network Constructed		90
	Network in Comercial Operation		80

Milestones	Start of Planning	[year]	2006
	Start of Implementation		2007
	Ready for Operation		2008
	End of Migration		2013

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	15000	820
	Cab Radios		1500	800
	Dispatchers		250	6

Additional Information

Pilot is finalised. Implementation is ongoing according to Plan. OBB is one of the first implementers of the ATCA platform - IP Based NSS components.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

BELGIUM

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year			
HSL Antwerp -The Netherlands border	50	2	Pilot	2007	Commercial operation	Loco	G2000	19	New	2009			
HSL Liège to German border	50	2	Pilot	2007									
Total	100				Total			19					
L36: Schaarbeek-Leuven	25	1	Contracted	2010	Contracted	Loco	HLE18* (ES60 U3)	120	New	2009			
L36 N: Schaarbeek-Leuven	25	1	Contracted	2010									
L35: Aarschot - Leuven	15	1	Contracted	2013	Contracted	Automotices	AM 08 (Desiro)	305	New	2011			
L139: Leuven - Ottignies	30	1	Contracted	2013									
L25 Antwerpen-Luchtbal- Antwerpen-Berchem	6	1	Contracted	2013	Contracted	Voitures pilotes	M6	4	New	2009			
L130: Auvelais - Namur	20	1	Contracted	2013									
L166: Dinant - Bertrix	73	1	Contracted	2013	Contracted	Loco	TRAXX**	40	Hired	2008			
L165: Bertrix - Athus	70	1	Contracted	2013									
L53: Mechelen - Leuven	24	1	Contracted	2013	Total			469					
L124+L130: Nijvel - Jemeppe/Sambre	48	1	Contracted	2013									
Total	336				*Will be in commercial operation from 2nd semester 2009 **Will be in commercial operation end of 2009								
L36+L37:Ans-Liège-Angleur	21	1	Planned	2015									
L25+L27: Antwerpen-Vilvoorde	85	1	Planned	2013									
L140: Ottignies-Fleurus	23	1	Planned	2013									
L147: Fleurus - Auvelais	9	1	Planned	2013									
L15: Antwerpen-Berchem - Lier	15	1	Planned	2013									
L16: Lier - Aarschot	25	1	Planned	2013									
L154: Namur - Dinant	28	1	Planned	2013									
L28: Schaarbeek - Brussel-Zuid	6	1		2015									
L50A: Brussel-Zuid - Denderleeuw	22	1											
L26: Vilvoorde - Linkebeek	12	1											
L124: Brussel-Zuid - Nijvel	28	1											
L161: Schaarbeek - Ottignies	30	1											
Port of Antwerp: L11,L11A,L10/2,L10	27	1	Planned	2015									
L96N: Lembeek - Brussel-Zuid	16	1											
L161: Ottignies - Namur	32	1	Planned	2013									
L144: Gembloux - Jemeppe/Sambre	15	1											
L162: Namur - Arlon (border to Luxemburg)	137	1											
L51(A): Zeebrugge - Brugge	14	1											
L50A: Brugge - Gent	41	1											
L58+L59: Gent - Antwerpen	64	1	Planned	2020									
L35: Aarschot - Hasselt	39	1											
L34+L24: Hasselt - Montzen	72	1											
L50+L53: Gent - Mechelen	57	1											
L15: Lier - Mol	41	1											
L19: Mol - Hamont (Dutch border)	34	1		2020									
Total	893												

Infrastructure

Total length of Rail Network	[km]	3400
Planned GSM-R		3000
Network Constructed		2800
Network in Commercial Operation		2020

Milestones

Start of Planning	[year]	2003
Start of Implementation		2005
End of Migration		2010


GSM-R

Mobile stations

		Planned	Activated
Mobile Users Planned	[unit]	5000	400
Cab Radios		2000	750
Dispatchers		250	12

Additional Information

Advanced Implementation Stage, ongoing according to plan.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%**
- 70 - 100%

BULGARIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Plovdiv junction (Plovdiv - Filipovo - Skutare - Plovdiv)	30	1	Commercial operation	2006	Commercial operation	2-Cab Loco	68E	58	Retrofitted	2005
Stara Zagora - Burgas	200	1	Commercial operation	2006	Commercial operation	2-Cab Loco	Erd 651CL1	31	Retrofitted	2005
Total	230				Commercial operation	EMU	3P 25	16	Retrofitted	2005
Plovdiv -Svilengrad - Turkish border	147	1	Contracted	2010	Total			105		
Total	147									
Plovdiv - Stara Zagora	114	1	Planned	2010						
Kalotina Zapad - Sofia	57	1	Planned	2013						
Sofia - Plovdiv	154	1	Planned	2015						
Vidin - Sofia	276	1	Planned	2020						
Sofia - Pernik - Radomir - Kulata	213	2	Planned	2020						
Mezdra - Gorna Oryahovitsa	206	2	Planned	2025						
Total	1020									


Infrastructure	Total length of Rail Network	[km]	4300
	Planned GSM-R (step1)		151
	Network Constructed		-
	Network in Comercial Operation		-

Milestones	Start of Planning	[year]	2006
	Start of Implementation		2007
	Ready for Operation		2010
	End of Migration		2011

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	175	-
	Cab Radios		15	-
	Dispatchers		22	-

Additional Information

General Project - "Reconstruction and electrification of 151 km line Plovdiv – Svilengrad", with GSM-R component; project dealine - November 2010. Actual stage for GSM-R - Preliminary design submitted.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

CHINA

Line	Section Length (km)	CTCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Wuhan-Guangzhou	1000	1	Contracted	2010	Contracted	HST	CRH 3 type	30	New	2008
Zhengzhou-Xi'an	458	2	Contracted	2010						
Shijiazhuang - Taiyuan	190	1	Contracted	2009	Contracted	HST	CRH 2 type	30	New	2008
Beijing - Jinan - Zhengzhou – Wuhan*	2132	1	Contracted	2009	Contracted	Other engines	Other engines	210		
Total	3780				Total			270		
Beijing - Tianjin	116	1	Commercial Operation	2008						
Total	116									

* Since no information was available on the precise path of this line, it is mentioned only in the tab.

Infrastructure	Total length of Rail Network	[km]	77084
	Planned GSM-R		2968
	Network Constructed		2665
	Network in Commercial Operation		2665

Milestones	Start of Planning	[year]	2003
	Start of Implementation		2004
	Ready for Operation		-
	End of Migration		-

GSM-R			Planned	Activated
Mobile stations	Mobile Users Planned	[unit]	700 000	-
	Cab Radios		20 000	907
	Dispatchers		140 000	-



CTCS implementation status

- Commercial operation L1
- ... Contracted or Planned L1
- Commercial operation L2
- ... Contracted or Planned L2
- Commercial operation L3
- ... Contracted or Planned L3

CROATIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Corridor X: Vinkovci - Tovarnik (state border)	34	1	Contracted	2008						
Total	34									
Corridor X: Savski Marof (state border) - Zagreb	26,8	1	Planned							
Corridor X: Zagreb - Dugo Selo	20,8	1	Planned							
Corridor X: Dugo Selo - Novska	84,2	1	Planned							
Corridor X: Zagreb - Sisak - Novska (parallel line with Zagreb - Dugo Selo - Novska)	117,4	1	Planned							
Corridor X: Novska - Vinkovci	151,1	1	Planned							
Corridor Vb: Botovo (state border) - Zagreb	79,1	1	Planned							
Corridor Vb: Zagreb - Karlovac	52,6	1	Planned							
Corridor Vb: Karlovac - Ogulin	56,5	1	Planned							
Corridor Vb: Ogulin - Rijeka (sea port)	119,7	1	Planned							
Corridor Vc: state border - Beli Manastir - Osijek	32,1	1	Planned							
Corridor Vc : state border - Beli Manastir - Osijek	18,4	1	Planned							
Corridor Vc: Strizivojna Vrpolje - Šamac - state border	22,7	1	Planned							
Corridor Vc: state border - Metković - Ploče (sea port)	22,8	1	Planned							
Total	804,2									

Infrastructure	Total length of Rail Network	[km]	2726
	Planned GSM-R		1280
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2004
	Start of Implementation		2010
	Ready for Operation		2011
	End of Migration		-

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	3320	-
	Cab Radios		520	-
	Dispatchers		13	-

Additional Information

Measurements of Coverage and Technical Documentation is finished for two corridors - 525 km.Tender for Pilot line is expected. Croatian Railways plan to start implementation of GSM-R network in the year 2010. The Pilot (part of corridor Vc) is expected to be finished end 2012.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

CZECH REPUBLIC

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Poříčany - Kolín	23.4	2	Pilot	2008	Pilot		362	1	Retrofitted	2007
Total	23.4				Pilot		Comuter unit 471	1	Retrofitted	2007
German border - Praha - Kolín	201	2	Planned	2013	Total			2		
Kolín - Brno - Austrian/Slovakian border	277	2	Planned	2011	Planned	HST	Unit 680	7	New	2006
Břeclav - Přerov	100	2	Planned	2013	Planned		Unit 471	1	Retrofitted	2008
Přerov – Petrovice u K.	106	2	Planned	2014	Planned	Loco	Unit 362	1	Retrofitted	2008
Border CZ/PL					Planned		Unit 363	31	Retrofitted	2013
Česká Třebová - Přerov	110	2	Planned	2014	Planned		Unit 380	20	New	2009
Praha-Plzeň	114	2	Planned	2015	Total			60		
Plzeň - Cheb	106	2	Planned	2015						
Dětmorovice – Mosty u Jablunkova – Border CZ/SK	53	2	Planned	2016						
Polanka nad Odrou – Český Těšín	39	2	Planned	2015						
Praha – České Budějovice	169	2	Planned	2015						
České Budějovice – Border CZ/A	57	2	Planned	2016						
Total	1332									


Infrastructure	Total length of Rail Network	[km]	9496
	Planned GSM-R		5400
	Network Constructed		537
	Network in Commercial Operation		210

Milestones	Start of Planning	[year]	2002
	Start of Implementation		2004
	End of migration (Voice, TEN-T)		2015
	End of Migration (GSM-R for ETCS)		2020

GSM-R Mobile stations		Planned	Activated
	Mobile Users Planned	1000	300
	Cab Radios	2000	162
	Dispatchers	-	68

Additional Information

Pilot Finalised. Follow up project – Completion of 1st National railway corridor: Kolín – Česká Třebová – Břeclav [A/SK] & Prague connecting lines, 327 km, close to finish, will be completed until January 2009. 2nd National railway corridor Břeclav [A/SK] – Přerov – Ostrava – Petrovice u Karviné [PL], 206 km: Public tender will be put out until end of 2008, realization 2009-2010



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

DENMARK

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Langå-Aalborg-Frederikshavn	194	2	Planned	2018	Planned	EMU	ER	44	Retrofitted	2016
Århus-Langå	46	2	Planned	2019	Planned	EMU	ET	34	Retrofitted	09/10
Fredericia-Århus	119	2	Planned	2019	Planned	DMU	MF	96	Retrofitted	2016
Fredericia - Odense	73	2	Planned	2019	Planned	DMU	MG	83	Retrofitted	2016
Odense-Ringsted-Roskilde	124	2	Planned	19/20	Planned	DMU	MP	23	Retrofitted	2016
Roskilde -København - Peberholm-Swedish border	72	2	Planned	2020	Total	Loco	ME	18	Retrofitted	2016
Padborg - Fredericia	111	2	Planned	2019				298		
Lunderskov-Esbjerg	58	2	Planned	2019						
København G Vigerslev-Hvidovre F	7	2	Planned	2020						
København H Helsingør	52	2	Planned	2021						
Ringsted- Nykøbing F	77	2	Planned	18/19						
Nykøbing F- Rødby	42	2	Planned	18/19						
Roskilde - Holbæk	57	2	Planned	2020						
Holbæk- Kalundborg	48	2	Planned	2020						
Bramming - Tønder	68	2	Planned	2021						
Vejle-Struer	148	2	Planned	2020						
Struer-Thisted	74	2	Planned	2021						
Langå-Struer	109	2	Planned	2020						
Skanderborg - Herning - Skjern	113	2	Planned	2021						
Esbjerg - Skjern - Holstebro	129	2	Planned	2021						
Odense - Svendborg	51	2	Planned	2021						
Sønderborg- Tinglev	41	2	Planned	2021						
Århus-Grenaa	71	2	Planned	2021						
Roskilde - Køge - Næstved	68	2	Planned	2017						
Total	1952									

Infrastructure	Total length of Rail Network	[km]	2133
	Planned GSM-R		2000
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2000
	Start of Implementation		2007
	Ready for Operation		2011
	End of Migration		2013

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	3100	-
	Cab Radios		1500	180
	Dispatchers		100	-

Additional Information

Finalization of radio planning documentation for the whole network, including ETCS Early Deployment and Private Railways is nearing completion. Work on the tender documents for both System Procurement and O&M is making good progress. The GSM-R frequencies have been leased.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

FINLAND

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Ring Rail Line Tikkurila - Vantaankoski	18	1 or 2	Planned	2019	Planned	EMU	Sm3	18	New	-
Helsinki - Tikkurila - Kerava	29	1 or 2	Planned	2019	Planned	EMU	Sm4	30	New	-
					Planned	Loco	Sr2	46	New	-
Kerava - Lahti	63	1 or 2	Planned	2019	Planned	DMU	Dm12	16	New	-
Lahti - Kouvola - Luumäki - Vainikkala	153	1 or 2	Planned	2019	Total			110		
Kouvola - Juurikorpi - Kotka/Hamina	70	1 or 2	Planned	2019						
Luumäki - Lappeenranta	27	1 or 2	Planned	2019						
Parikkala - Joensuu	130	1 or 2	Planned	2019						
Pieksämäki - Iisalmi	174	1 or 2	Planned	2019						
Total	664									


Infrastructure	Total length of Rail Network	[km]	5820
	Planned GSM-R		4970
	Network Constructed		4700
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2001
	Start of Implementation		2003
	Ready for Operation		2009
	End of Migration		2010

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	3200	100
	Cab Radios		1000	3
	Dispatchers		-	64

Additional Information

Advanced implementation stage. BTS volume implementation mainly finished end 2008.GSM-R network (including dispatcher systems) is ready for country wide service beginning 2009.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

FRANCE

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Paris - Strasbourg HSL	300	2	Contracted	2009	Contracted	HST	TGV POS	19	New	2010
Total	300				Contracted	HST	TGV PBA	9	Retrofitted	2009
Rhin - Rhône East HSL	140	2	Planned	2012	Contracted	HST	TGV	17	Retrofitted	2009
Contournement Nîmes - Montpellier HSL	50	1 ou 2	Planned	2016			PBKA			
Paris - Lyon HSL	485	2	Planned	2018	Contracted	HST	TGV Dasye	49	New	2011
South Europe Atlantique HSL	300	2	Planned	2016						
Bretagne - Pays de Loire	200	2	Planned	2015						
HSL Atlantique (Paris-Le Mans/Paris -Tours)	282	2	Planned	2017	Total			93		
Lyon - Torino Tunnel	50	2	Planned	2020						
Luxembourg to Switzerland via Metz & Strasbourg	424	1	Planned	2015						
Belgium to Lyon	821	1	Planned	2020						
Lyon to Italy	253	1	Planned	2015						
Lyon to Spain and Marseille	669	1	Planned	2020						
International section of Paris Francfort corridor	56	1	Planned	2012						
Feeding branches from Corridor D to port or freight terminal areas of Marseille	10	1		2020						
Feeding branches from Corridor D to freight terminal areas of Avignon	3.5	1		2020						
Feeding branches to port or freight terminal areas of Le Havre (Le Havre - Amiens - Lille)	312	1	Planned	2020						
Feeding branches to freight terminal areas of Calais (Calais - Lille - Metz)	382	1	Planned	2020						
Feeding branches to freight terminal areas of Paris (Paris - Amiens)	133	1	Planned	2020						
Total	4570.5									


Infrastructure	Total length of Rail Network	[km]	32 000
	Planned GSM-R		14 400
	Network Constructed		2160
	Network in Commercial Operation		1700

Milestones	Start of Planning	[year]	2000
	Start of Implementation		2003
	Ready for Operation		-
	End of Migration		2014

GSM-R Mobile stations		Planned	Activated
	Mobile Users Planned	[unit]	-
	Cab Radios	10 000	3000
	GSM-R Line side Telephone Sets	6000	2215
	Dispatchers	-	48

Additional Information

Step 1 (Tranche 1 - Eastern Part Roll Out) is under development, end of roll out expected mid 2009; for the rest of the network planned, the PPP - Private-Public Partnership is in final stage to be signed.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70 %
- 70 - 100 %

GERMANY

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Berlin - Halle/Leipzig	135	2	Commercial operation	2006	Commercial operation	Loco	BR101	5	Retrofitted	2005
Total	135									
High Speed French Border - Saarbrücken - Mannheim	128	1 and 2	Contracted	2010	Commercial operation	HST	BR401 (ICE1)	19	Retrofitted	2006
High Speed Nürnberg -Ingolstadt - München	170	2	Contracted	2010	Commercial operation	Loco	BR189	26	Retrofitted	2007
Total	298				Commercial operation	Loco	BR185	10	Retrofitted	2007
Aachen - Belgian border	8	1	Planned	2009	Contracted	Loco	BR189	18	Retrofitted	2009
High Speed Leipzig - Erfurt - Nürnberg	400	2	Planned	2017	Contracted	HST	BR409 (Thalys)	2	Retrofitted	2009
Berlin - Rostock	120	1 LS	Planned	12 or 15	Contracted	HST	BR406 (ICE3)	6	Retrofitted	2011
High Speed 3rd track Stelle - Lüneburg	30	2	Planned	2015	Contracted	HST	BR406 (ICE3)	11	Retrofitted	2011
High Speed Berlin-Dresden	125	2	Planned	2018	Contracted		BR400	22	Retrofitted	2008
Conventional Emmerich - Basel	680	1 LS and 2	Planned	2015	Total			59		
					Planned	HST	BR411	58	Retrofitted	10/15
					Planned	HST	BR415	11	Retrofitted	2015
					Planned	Loco	BR152	170	Retrofitted	18/20
					Planned	Loco	BR182	25	Retrofitted	2013
					Planned	Loco	BR185	372	Retrofitted	13/20
Conventional Aachen - Frankfurt (Oder)/Horka	1000	1 LS and 2	Planned	2020	Planned	Loco	BR186	20	Retrofitted	18/20
Total	2363				Planned	Loco	BR189	46	Retrofitted	10/20
					Planned	E-Loco		210	New	20/22
					Planned	Single cab unit	Driving T.	90	Retrofitted	20/22
					Planned	HST	BR403	50	Retrofitted	16/19
					Planned	EMU	EMU	501	Retrofitted	20/22
					Planned		BR18x	258	New	13/20
					Planned		E-Loco	111	New	20/26
					Planned		ICE X	130	New	13/18
					Planned		Successor ICE 1/2	90	New	18/26
					Planned	EMU	EMU	247	New	24/27
					Total			2389		


Infrastructure	Total length of Rail Network	[km]	36 000
	Planned GSM-R		29 300
	Network Constructed		25 145
	Network in Commercial Operation		24 710

Milestones	Start of Planning	[year]	2000
	Start of Implementation		2004
	Ready for Operation		2005
	End of Migration (Step 1)		2007

GSM-R			Planned	Activated
	Mobile stations			
	Mobile Users Planned	[unit]	-	31 346
	Cab Radios		-	14 846
	Dispatchers		-	421

Additional Information

Step 1- 24300 km was finalised end 2007. Step 2, additional # 5000 km are in implementation phase. Application for additional GSM-R frequencies (# MHz paired in the PMR/PAMR Band(Trunk Band)) sent to regulator. National designation expected soon.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

GREECE

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
SKA - Airport	40	1	Under test	2009	Contracted	DMU	GTW2/6	12	Retrofitted	2010
SKA - Korinth - Kiato	110	1	Under test	2009			Rail bus			
Total	150				Contracted	DMU	GTW2/6	5	Retrofitted	2010
Piraeus - Athens - SKA	18	1	Contracted	2009			Rail bus			
SKA - Tithorea	148	1	Contracted	2010	Contracted	DMU	Man 2000	15	Retrofitted	2010
Inoi - Chalkida	22	1	Contracted	2010	Contracted	Loco	Adtranz	36	Retrofitted	2010
Domokos - Platy	195	1	Contracted	2010			DE2000			
Platy - Thessaloniki	41	1	Contracted	2010			IC200N			
Thessalonki - Promachonas	140	1	Contracted	2010	Contracted	DMU	Intercity	16	Retrofitted	2010
Total	564						AEG DE-IC200N			
Thessaloniki - Idomeni	79	1	Planned	2010	Contracted	Loco	High Performance Loco120	30	Retrofitted	2010
Total	79						Hellas Sprinter			
					Contracted	EMU	DESIRO	20	Retrofitted	2010
					Total			134		

Infrastructure	Total length of Rail Network	[km]	950
	Planned GSM-R		707
	Network Constructed (GSM-R)		-
	Network in Comercial Operation		-

Milestones	Start of Planning	[year]	2006
	Start of Implementation		2007
	Ready for Operation		2009
	End of Migration		2011

GSM-R			Planned	Activated
Mobile stations	Mobile Users Planned	[unit]	10 000	-
	Cab Radios		630	3
	Dispatchers		50	-

Additional Information

The network implementation is ongoing.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

HUNGARY

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
(Vienna -) Hegyeshalom - Budapest	190	1	Commercial operation	2007	Commercial operation	Loco	V63	17	Retroffited	2005
Hodos - Zalacséb-S.	27	1	Commercial operation	2003				17		
Total	217									
Rajka - Hegyeshalom	15	2	Planned	2013						
S z a j o l - D e b r e c e n - Nyíregyháza-Záhony	226	2	Planned	2013						
Boba – Székesfehérvár	120	2	Planned	2013						
Székesfehérvár – Budapest	60	2	Planned	2013						
Győr – Celldömölk - Boba	82	2	Planned	2013						
Boba - Hodos	104	2	Planned	2013						
Budapest- Cegéd-Szajol-Lököshazája	225	2	Planned	2013						
Total	832									


Infrastructure	Total length of Rail Network	[km]	7500
	Planned GSM-R		4360
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2007
	Start of Implementation		2009
	Ready for Operation		2009
	End of Migration		2013

GSM-R Mobile stations	Mobile Users Planned	[unit]	Planned	Activated
	Cab Radios		14 800	-
	Dispatchers		1500	-
			-	-

Additional Information

The GSM-R tender for Step 1 is in final phase.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

GSM-R is planned for 3200 km. The implementation is on-going.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Torino-Novara	90	2	Commercial operation	2006	Commercial operation	EMU	ETR470	15	Retrofitted	2002
Roma-Napoli	200	2	Commercial operation	2005	Commercial operation	EMU	ETR485	15	Retrofitted	2007
Milano - Bologna	182	2	Commercial operation	2008	Commercial operation	EMU	ETR500	30	Retrofitted	2005
Total	472				Commercial operation	EMU	ETR500	30	Retrofitted	2005
Bologna - Florence	90	2	Contracted	2009	Commercial operation	EMU	ETR600	12	New	2006
Novara - Milan	34	2	Contracted	2009	Commercial operation					
Milan - Verona	112	2	Contracted	2013	Commercial operation	EMU	ETR610*	14	New	2009
Verona - Padova	77	2	Contracted	2013	Commercial operation					
Total	313				Commercial operation					
Roma - Florence	260	2	Planned	2011	Commercial operation	Loco	Mitsui 189	15	Retrofitted	2009
Corridor A	520	1	Planned	2015	Total Contracted Total <small>*In pre operation ** Due in operation April 2009</small>					
Corridor B	428	1	Planned	2014						
Corridor D	361	1	Planned	2014		Loco	E403 **	15	Retrofitted	2009
Total	1569							131 15		

Infrastructure	Total length of Rail Network	[km]	16 500
	Planned GSM-R		9600 + 599
	Network Constructed		8500 + 480
	Network in Comercial Operation		8500 + 480
	(Conventional Line +HSL)		

Milestones	Start of Planning	[year]	2001
	Start of Implementation		2001
	Ready for Operation		2004
	End of Migration		2007

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	6000	3000
	Cab Radios		3450	650
	Dispatchers		1500	800

Additional Information

The GSM-R services are in operation on the whole commercial network (8300 km) and on additional 200 Km of low traffic side-lines. The GSM-R coverage project of additional 1100 Km (secondary lines) have been finalised (Project Targeted deadline: 1° Quarter 2010).



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

LITHUANIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
state border -Marijampolė	40	2	Planned	2015						
Vilnius - Kaunas, Vilnius - Kena, Kyviškes - Valčiūnai - Paneriai, Kaunas - Kybartai	270	1	Planned	2022						
Kaišiadorys - Radviliškis, Šiauliai - Klaipėda, Gaižiūnai - Palemonas	316	1	Planned	2025						
Total	626									


Infrastructure	Total length of Rail Network	[km]	1780
	Planned GSM-R		1179
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	-
	Start of Implementation		2008
	Start of Migration		2011

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	-	-
	Cab Radios		-	-
	Dispatchers		-	-

Additional Information

The GSM-R tender was granted middle 2008, implementation have started.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

LUXEMBOURG

Line	Section Length (km)	ETCS Level	Status	Year		Status	Railcar Type	Model name	Quantity	Origin	Year
Bettembourg - Dudelange/Usines -Volme-range	6	1	Commercial operation	2007		Commercial operation	EMU	CFL 2000 Type Z2	4	Retrofitted	2004
Luxembourg – Bettembourg frt. (Luxembourg - Berchem - Bettembourg frt.)	11	1	Commercial operation	2007		Commercial operation	Loco	CFL 3000	3	Retrofitted	2005
Ettelbruck - Luxembourg (Luxembourg - Dommeldange, Lorentzweiler, Mersch, Cruchten Ettelbruck)	40	1	Commercial operation	2005		Commercial operation	EMU	CFL 2000 Type Z2	18	Retrofitted	2006/2007
						Total			25		
						Planned	EMU	CFL 2200 Type TER2-ng	12	Retrofitted	2011
						Planned	Loco	CFL 4000	20	Retrofitted	2010
						Planned	Single Cab Unit	CFL	20	Retrofitted	2010
Luxembourg – Oetrange (Luxembourg - Sandweiler)	10	1	Commercial operation	2005		Planned	Unit	Trailer 2N	16	Retrofitted	2011
						Total	Loco	CFL 3000			
Luxembourg Station	-	1	Commercial operation	2006					68		
Total	67										
The remaining part of the network	214	1	Contracted	2010							
Total	214										


Infrastructure	Total length of Rail Network	[km]	275
	Planned GSM-R		275
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	-
	Start of Implementation		-
	Ready for Operation		-
	End of Migration		-

GSM-R Mobile stations	Mobile Users Planned	[unit]	Planned	Activated
	Cab Radios		-	-
	Dispatchers		-	-
			-	-

Additional Information

Radio planning made.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

GSM-R				
Mobile stations	Mobile Users Planned	[unit]	Planned	Activated
	Cab Radios		-	-
	Dispatchers		-	-



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

NORWAY

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Østfoldbanen østre linje	80	2	Planned	2012	Planned	EMU	Type 69	51	Retrofitted	2015
(Moss)-Kornsjø	109	2	Planned	2015	Planned	EMU	Type 70	16	Retrofitted	2015
(Ski)-Moss, Lillestrøm-Charlot- tenberg gr.	150	2	Planned	2016	Planned	EMU	Type 72	36	Retrofitted	2015
(Oslo)-Alna - Lillestrøm (inkl. Alnabru og Loenga)	51.9	2	Planned	2017	Planned	EMU	Type 73	22	Retrofitted	2015
Hokksund - Kongsberg - Nordagutu, (Tønsberg)-(Nor- dagutu),	245.9	2	Planned	2018	Planned	DMU	Type 93	15	Retrofitted	2020
(Nordagutu)-Kristiansand, (Drammen)-Hokksund - Hønefoss	351.7	2	Planned	2019	Total	Loco	E118	22	Retrofitted	2015
(Kristiansand)-Stavanger	230.5	2	Planned	2020						
(Eidsvoll)-Hamar	58.6	2	Planned	2021						
(Dombås)-Trondheim	210.8	2	Planned	2022						
Jessheim-Eidsvoll, (Hamar)- Dombås, (Oslo)-Roa, Roa-Hø- nefoss	327.5	2	Planned	2023						
(Hønefoss)-Bergen	492.9	2	Planned	2024						
Narvik-Bjørnfjell	43.5	2	Planned	2025						
(Oslo)-Gardemoen-Eidsvoll	65.1	2	Planned	2026						
Osloområdet (GS-anlegget), (Oslo)-Ski	58.2	2	Planned	2027						
(Oslo)-Asker, Asker-Drammen, Drammen-Tønsberg, Hell- Storlien gr., (Sandvika)-(Asker) og Askerbanen, (Asker)-Spik- kestad	262.5	2	Planned	2028						
	550.5	2	Planned	2029						
Røros-Støren, (Trondheim)- Grong, Hamar-Elverum-Røros (Grong)-Mo i Rana, Mo i Rana- Bodø	508.8	2	Planned	2030						
Total	3797.4									

Infrastructure	Total length of Rail Network	[km]	4077
	Planned GSM-R		3800
	Network Constructed		3800
	Network in Commercial Operation		3800

Milestones	Start of Planning	[year]	1998
	Start of Implementation		2003
	Ready for Operation		-
	End of Migration		2007

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	5000	4420
	Cab Radios		2000	1434
	Dispatchers		16	16

Additional Information

Migrated to GSM-R end 2007. New features for on board staff implemented end 2008.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

POLAND

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Legnica –Miłkowice	9,826	2	Planned	2009	Planned	Loco	SU 46	2	Retroffited	2009
Miłkowice – Chojnów	8,473	2	Planned	2009	Planned	Loco	ET 22	2	Retroffited	2009
Chojnów – Okmiany	12,127	2	Planned	2009	Planned	Loco	EN 57	2	Retroffited	2009
Okmiany – Bolesławiec	14,99	2	Planned	2009	Planned	Loco	EU07/EU	2	Retroffited	2009
Bolesławiec – Zebrzydowa	13,708	2	Planned	2009	Total		08	8		
Zebrzydowa – Węgliniec	12,203	2	Planned	2009						
Węgliniec – Bielawa Dolna	12,544	2	Planned	2009						
Bielawa Dolna – Country Border	0,529	2	Planned	2009						
Trakisзки – Suwalki – Sokółka – Białystok – Malkinia - Warszawa	340,4	2	Planned							
Grodzisk Mazowiecki – Zawiercie	224	1	Planned							
Total	648,8									


Infrastructure	Total length of Rail Network	[km]	19 500
	Planned GSM-R		15 000
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2007
	Start of Implementation		2008
	Ready for Operation		2010
	End of Migration		2015

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	40 000	-
	Cab Radios		6500	-
	Dispatchers		300	-

Additional Information

The first GSM-R Pilot, intended to be multivendor, is in tender process.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

PORTUGAL

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
High Speed Lisboa - Porto	300	2	Planned	2015	Planned	DMU	-	25	New	2009
High Speed Lisboa - Madrid	200	2	Planned	2013	Planned	EMU	-	36	New	2009
High Speed Porto - Vigo	100	2	Planned	2013	Total			61		
High Speed Aveiro - Salamanca		2	Planned							
High Speed Évora - Faro		2	Planned							
Huelva Corridor										
Conventional North South	640	1	Planned							
Corridor Porto - Sines										
Conventional South transversal Corridor	200	1	Planned	2013						
Sinez - Elvas										
Conventional North transversal Corridor	200	1	Planned							
Pampilhosa - Vilar Formoso -Salamanca										
Total	1040									


Infrastructure	Total length of Rail Network	[km]	3600
	Planned GSM-R		2600
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2007
	Start of Implementation		2009
	Ready for Operation		-
	End of Migration		2014

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	-	-
	Cab Radios		650	-
	Dispatchers		-	-

Additional Information

Final decision taken to install GSM-R all conventional line and on the HSL. Possible installation of GSM-R on some of the secondary lines in a second phase.Tender process for NSS started. National Telecomms GSM-R operation license for Refer Telecom in discussion be discussed until end 2008



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

ROMANIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Chitila - Crivina	30	2	Pilot							
Total	30									
Bucharest - Campina	92	1	Commercial operation	2004						
Total	92									
(Curtici -) Bekeskaba - Simeria	175	2	Planned	2010						
Simeria -Sighisoara - Brasow	310	2	Planned	2010						
Bukarest - Fetesti	150	1	Planned	2009						
Fetesti - Constanta	80	1	Planned	2009						
Total	715									

Infrastructure	Total length of Rail Network	[km]	11 380
	Planned GSM-R		750
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	2008
	Start of Implementation		2009
	Ready for Operation		-
	End of Migration (Corridors)		2015

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	-	-
	Cab Radios		-	-
	Dispatchers		-	-

Additional Information

The ERTMS L2 Pilot, with GSM-R component, is expected to be tendered first part of 2009.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

SAUDI ARABIA

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Riyadh - Dammam	449	1	Contracted	2008	Contracted	-	-	15	Retroffited	2010
Makkah-Madinah Link	444	1	Contracted	2012	Total			15		
North-South Railway project*	1600	2	Contracted	2012						
Total	2493									
* This line doesn't appear on the map as its georeferenced path is not available yet.										


Infrastructure	Total length of Rail Network	[km]	-
	Planned GSM-R		-
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	-
	Start of Implementation		-
	Ready for Operation		-
	End of Migration		-

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	-	-
	Cab Radios		-	-
	Dispatchers		-	-

Additional Information

Saudi Railway Organisation commissioned a GSM-R project for the Dammam to Riyadh line in 2005.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

56 : SLOVAKIA											
Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year	
Leopoldov - Nové M.n.V.* Total	36 36	1	Pilot	2009	Planned Total	Loco	-	18 18	Retrofitted	2012	
Brat. hl. st.-Leopoldov	64	1	Commercial Operation	2009							
Total	64										
Poprad – Margecany	66	2	Planned	2020							
Margecany – Kysak	19	2	Planned	2020							
Kysak – Košice	16	2	Planned	2015							
Košice – Barca St.1	4	2	Planned	2025							
Barca St.1–Čierna n. T.	91	2	Planned	2025							
Zwardoň - Skalité	7	2	Planned	2020							
Skalité - Čadca	13	2	Planned	2020							
Čadca - Žilina	31	2	Planned	2015							
Breclav - Kúty	7	2	Planned	2015							
Kúty – Dev. N. V.	51	2	Planned	2015							
Marchegg – Dev. N. V.	4	2	Planned	2015							
Dev. N. V. – Bratislava	13	2	Planned	2015							
Brat. hl. st. – Brat. Petrž.	18	2	Planned	2015							
Brat. Petrž. – Rajka	15	2	Planned	2015							
Brat. Petrž. – Kittsee	2	2	Planned	2015							
Brat. hl. st. - Galanta	49	2	Planned	2018							
Galanta – Nové Zámky	42	2	Planned	2018							
Nové Zámky–Komárno	29	2	Planned	2020							
Komárno – Komárom	5	2	Planned	2020							
Nové Zámky – Štúrovo	44	2	Planned	2020							
Štúrovo – Szob	14	2	Planned	2020							
Nové M.n.V. - Púchov	59	2	Planned	2015							
Púchov – Žilina	44	2	Planned	2018							
Žilina – Vrútky	21	2	Planned	2020							
Vrútky – Štrba	101	2	Planned	2020							
Štrba – Poprad	19	2	Planned	2020							
Total	784										
*This section is expected to be in commercial operation by May-June 2009											


Infrastructure	Total length of Rail Network	[km]	3477
	Planned GSM-R		-
	Network Constructed		25
	Network in Commercial Operation		25

Milestones	Start of Planning	[year]	-
	Start of Implementation		2005
	Ready for Operation		-
	End of Migration		-

GSM-R Mobile stations		Planned	Activated
	Mobile Users Planned	[unit]	-
	Cab Radios		-
	Dispatchers		-

Additional Information

Part of the Pilot (Bratislava to Nove Zámky) deployed - Bratislava to Senec.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70 %
- 70 - 100 %

GSM-R		Planned	Activated
Mobile stations	Mobile Users Planned	2700	-
	Cab Radios	410	-
	Dispatchers	170	-



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned**
- 0 - 30 %
- 30 - 70%
- 70 - 100%

SPAIN

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Albacete - La Encina	93	1	Pilot		Commercial operation	HST	S-103	16	-	2004
Total	93									
Madrid - Zaragoza - Lérida	460	1*	Commercial operation	2006	Commercial operation	HST	S-102 Duck	16	-	2005
Lérida - Tarragona - Barcelona	190	1*	Commercial operation	2008	Commercial operation	HST	S-120 Shuttle	12	-	2006
Madrid Valladolid	180	1*	Commercial operation	2007	Commercial operation	HST	S-104 Shuttle	33	-	2008
Córdoba - Málaga	155	1*	Commercial operation	2007	Commercial operation	HST	S-121	6	-	2009
Total	985				Total			83		
Zaragoza Huesca	79,5	1	Contracted	2006	Contracted	HST	S-102	30	-	
International Section	44,5	1 and 2	Contracted	2006			(S/112)			
Perpignan Figueres					Contracted	HST	S-103 ICE	10	-	
La Sagrada - Toledo	21	1 and 2	Contracted	2006	Contracted	HST	S-120	16	-	
Madrid commuters lines	160	1 and 2	Contracted	2008	Contracted	HST	S-121	23	-	2009
Madrid - Albacete - Valencia	470	1 and 2	Contracted	2008	Contracted	HST	S/114	13	-	
					Contracted	HST	S-130	45	-	2009
Barcelona - Figueras	132	1 and 2	Contracted	2008			Duckling			
Total	907				Contracted	HST	S-100TGV	24	-	
* These lines will switch to level 2 soon					Contracted	HST	S-490Alaris	10	-	
					Contracted	EMU	S-446	31	-	2010
					Contracted	EMU	S-447	43	-	2010
					Contracted	EMU	S-450	20	-	2010
					Contracted	EMU	S-465 Civia	123	-	2010
					Total			388		
					Planned	Loco	252	15	-	
					Planned	Loco	253	15	-	
					Total			30		

Infrastructure	Total length of Rail Network	[km]	11 775 + 1530
	Planned GSM-R		8659 + 1530
	Network Constructed		22 + 1530
	Network in Comercial Operation (Conventional Line +HSL)		22 + 1530

Milestones	Start of Planning	[year]	2000
	Start of Implementation		2003
	Ready for Operation		2003
	End of Migration		2006

GSM-R			Planned	Activated
Mobile stations	Mbile Users Planned	[unit]	-	1900
			-	700
	Cab Radios		-	10
	Dispatchers			

Additional Information

5 Projects (2459 km) for Conventional Lines are ready to be tendered; HSL Madrid-Valencia (450 Km) in construction (Q2 2010)




ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%**
- 70 - 100%

GSM-R		Planned	Activated
Mobile stations	Mobile Users Planned [unit]	-	-
	Cab Radios	-	-
	Dispatchers	-	-



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

SWEDEN

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Botnia Line (Umea - Ornskoldsvik - Västeras-pby)	190	2	Contracted	2010	Planned Total	EMU	X61	48 48	New	-
West Dalarna Line (Rep-bäcken - Malung)	134	3	Contracted	2010						
Ådalsbanan (Sundsvall - Västeras-pby)	180	2	Contracted	2010						
Haparandabanan (Boden - Haparanda)	156	2	Contracted	2011						
Malmö Central Station Upgrade	10	1	Contracted	2012						
City Tunnel project	6	2	Contracted	2012						
The remaining part of the network	2218	2 or 3	Planned*	2030						
Total	2894									

*These sections are closer to the "Contracted" than to the "Planned" status, although no contract has been awarded yet to a specific supplier. The time frame mentioned depends on the Swedish deployment plan.

Infrastructure	Total length of Rail Network	[km]	10 000
	Planned GSM-R		9850
	Network Constructed		8500
	Network in Commercial Operation		8500

Milestones	Start of Planning	[year]	1997
	Start of Implementation		2000
	Ready for Operation		-
	End of Migration		2007

GSM-R Mobile stations	Mobile Users Planned	[unit]	Planned 7000	Activated 4300
	Cab Radios		-	2130
	Dispatchers		-	80

Additional Information

The Swedish Network is finalised end 2007.



ETCS implementation status


- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

Additional Information

Advanced implementation stage. The project is on track in terms of dates.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3


GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%**
- 70 - 100%

Note: only the high speed Taipei-Kaohsiung was represented as the georeferenced map of the overall network is not available yet.

Milestones	
Start of Planning	[year]
Start of Implementation	-
Ready for Operation	-
End of Migration	-

GSM-R				
Mobile stations	Mobile Users Planned	[unit]	Planned	Activated
	Cab Radios		-	-
	Dispatchers		-	-



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

THE NETHERLANDS

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Betuwe Line Rotterdam - Zevenaar	110	2	Commercial operation	2007	Contracted	EMU	Série 189	46	Retrofitted	2008
Total	110				Contracted		DE6400	22	Retrofitted	2008
Amsterdam - Utrecht	30	2	Contracted	2009	Contracted		Sprinter	35		2008
HSL South Amsterdam	93	2	Contracted	2008			Light Train			
Belgian border					Contracted		Class 66s/G1 206	23	Retrofitted	2008
Total	123				Total			126		

Infrastructure	Total length of Rail Network	[km]	3050
	Planned GSM-R		3050
	Network Constructed		3050
	Network in Commercial Operation		3050

Milestones	Start of Planning	[year]	1999
	Start of Implementation		2001
	Ready for Operation		2003
	End of Migration		2006

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	8000	6900
	Cab Radios		2500	2500
	Dispatchers		200	2

Additional Information

Teleraail - Old Analogue Radio Network switched off beginning 2007. Interconnection lines with Germany, Belgium in operation. Roaming with Germany, Belgium, Franc and Switzerland in operation. Roaming with at least Italy and Austria is planned for 2009.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
HS Ankara - Istanbul 1st phase (Sincan-Esenkent and Hasanbey-Inönü)	57	1	Contracted	2010	Contracted	HST	YHT65000	12	New	2007
HS Ankara - Istanbul 1st phase (Esenkent-Hasanbey)	196	1	Contracted	2009						
HS Ankara - Istanbul 2nd phase (Inönü-Vezirhan)	54	1	Contracted	2011						
HS Ankara - Istanbul 2nd phase (Vezirhan-Köse-koy)	95	1	Contracted	2011						
HS Ankara - Konya	212	1	Contracted	2010						
Bogazkopru-Yenice ve Mersin Toprakkale	419	1	Contracted	2012						
HS Ankara - Istanbul 2nd phase (Gebze-Halkali)	77	1	Contracted							
Total	1110									
HS Ankara - Istanbul 2nd phase (Köse-koy-Gebze)	56	1	Planned							
HS Ankara - Sivas	554	1	Planned							
Total	610									

Infrastructure	Total length of Rail Network	[km]	-
	Planned GSM-R		-
	Network Constructed		-
	Network in Commercial Operation		-

Milestones	Start of Planning	[year]	-
	Start of Implementation		-
	Ready for Operation		-
	End of Migration		-

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	-	-
	Cab Radios		-	-
	Dispatchers		-	-

Additional Information

Two GSM-R projects Ankara – Eskisehir and Palatli – Konya have started.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)

- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%

UNITED KINGDOM

Line	Section Length (km)	ETCS Level	Status	Year	Status	Railcar Type	Model name	Quantity	Origin	Year
Cambrian Line : Shrewsbury to Machynlleth, then North to Pwllheli to Aberystwth	218	2	Contracted	2009	Contracted	DMU Loco	Class 158 Class 37	17	Retrofitted Retrofitted	2008 2008
					Total			4		
					Planned			21		
					Planned			186		
					Planned			165		
London - Bristol	200	2	Planned	2017	Planned	DMU		75	Retrofitted	2015-2016
					Planned			21		
					Planned			19		
					Planned			139		
					Planned			27		
London - Doncaster	250	2	Planned	2018	Planned	DMU		51	Retrofitted	2017-2018
					Planned			14		
					Planned			14		
					Planned			40		
					Planned			67		
Total	450				Planned	DMU		26	Retrofitted	2024-2027
					Planned			40		
					Planned			112		
					Planned			36		
					Planned			182		
					Planned	DMU		44	Retrofitted	2021-2027
					Planned			29		
					Planned			172		
					Planned			8		
					Planned			157		
					Planned	DMU		43	Retrofitted	2020-2023
					Planned			32		
					Planned			25		
					Planned			100		
					Planned			415		
					Planned	Loco		30	Retrofitted	2012-2017
					Planned			46		
					Planned			96		
					Planned			14		
					Planned			34		
					Planned	HST		44	Retrofitted	2016-2020
					Planned			27		
					Planned			53		
					Planned			613		
					Planned			1344		
					Planned	Loco		414	New	2008-2020
					Planned			376		
					Planned			Track Plant		
					Total			5165		

Infrastructure	Total length of Rail Network	[km]	16 450
	Planned GSM-R		14 780
	Network Constructed		9699
	Network in Commercial Operation		464

Milestones	Start of Planning	[year]	2000
	Start of Implementation		2002
	Ready for Operation		2011
	End of Migration		2014

GSM-R Mobile stations			Planned	Activated
	Mobile Users Planned	[unit]	19 000	8452
	Cab Radios		8790	102
	Dispatchers		1000	20

Additional Information

GSM-R in implementation stage, all over the network. End 2008 results: Routeworks 65% complete; core transmission rings in the south are priority commissioning. Sitework 30% complete with priority to work in the south & TENS routes. 100 sites completed before end 2008.



ETCS implementation status

- Commercial operation L1
- - - Contracted or Planned L1
- Commercial operation L2
- - - Contracted or Planned L2
- Commercial operation L3
- - - Contracted or Planned L3

GSM-R implementation status (% of the national railway network)


- planned
- 0 - 30 %
- 30 - 70%
- 70 - 100%


Some statistics on ETCS

We present here below the global figures on ETCS at a worldwide level. Since the last edition, new lines were put in commercial operation (revenue service): they are detailed in the following table.

Country name	Line	Section length (km)	Maximum speed (km/h)	ETCS Level
Austria	Wien to Hungarian border section Hegyesschalom	67	160	1
Bulgaria	Plovdiv Junction (Plovdiv - Filipovo - Skutare - Plovdiv)	30	-	1
	Stara Zagora - Burgas	200	200	1
Hungary	Hodos - Zalacséb-S.	27	120	1
	(Vienna -) Hegyeshalom - Budapest	190	160	1
Luxembourg	Bettembourg - Dudelange/Usines -Volmerange	6	80	1
	Luxembourg – Oetrange (Luxembourg - Sandweiler)	10	120	1
	Luxembourg – Bettembourg frt. (Luxembourg - Berchem - Bettembourg frt.)	11	140	1
	Ettelbruck - Luxembourg (Luxembourg - Dommeldange, Lorentzweiler, Mersch, Cruchten Ettelbruck)	40	120	1
	Luxembourg Station	-	120	1
Romania	Bucharest - Campina	92	160	1
Slovakia	Brat. hl. st.-Leopoldov	64	160	1
Spain	Madrid - Valladolid	180	300	1
	Córdoba -Málaga	155	300	1
	Lérida - Tarragona - Barcelona	190	300	1
	Madrid - Zaragoza - Lérida	460	300	1
Total Europe Level 1		1722		
Germany	Berlin - Halle/Leipzig	135	200	2
Italy	Milano – Bologna	182	300	2
	Roma-Napoli	200	300	2
	Torino-Novara	90	300	2
The Netherlands	Betuwe Line Rotterdam - Zevenaar	110	120	2
Switzerland	Mattstetten Rothrist (Olten - Berne)	45	200	2
	Löstchberg base tunnel between Frutigen - Visp (Bern - Brig)	35	250	2
Total Europe Level 2		797		
Total Europe		2519		
China	Beijing - Tianjin	116	350	1
India	Chennai -Gummudipundi	50	80	1
South Korea	HSR Gyeongbu Phase 1 (Seoul-Deagu)	238,6	300	1
Taiwan	Total network	1200	-	1
Total Asia		1604,6		

The following maps are an illustration of the situation, with a zoom on the European map, representing all the projects.





Along with these already operated lines, many other sections were contracted to suppliers to equip them with ETCS. For Europe, the breakdown between the levels is as follows:

- 1768,5 km of ETCS Level 1;
- 2621,5 km of ETCS Level 2 ;
- 134 km of Level 3/Regional.

Zone/Country	Europe	Algeria	China	India	Mexico	Saudi Arabia	South Korea	Turkey
Contracted sections (km)	4524	426	3780	196	35	2493	404	1110

After contract awarding, and before putting into commercial service, the section is tested during a certain period. These non-commercially operated but nevertheless equipped lines represent 515 km in Europe, and 40 km in Australia.

In addition to these sections, one can also mention the priority lines that will be potentially equipped with ETCS, but for which no contract has been awarded yet (international corridors are typically classified within this category): 610 km outside Europe (Turkey mainly), and 31359 km in Europe in the long term (some countries transmitted plans up to 2030).

This leads to a total of 7558 km of lines directly impacted by ERTMS in Europe, and 10049 km outside Europe.

However, this classification does not always fit to each national context; in particular, there is in Europe a certain number of sections classified as “planned” which are rather closer to the *Contracted* status. When this is taken in account, it can be reasonably considered that in Europe, there are actually 9776 km of lines that are concerned by ERTMS for the short and medium term.

In Europe there are 1009 engines in commercial service with ERTMS, to which we can add 1305 contracted (either retrofitted or newly bought) engines. The table below gives the amount of rolling-stock directly concerned by ERTMS at a worldwide level, including the rolling stock under the *pilot/test* status. Spain is playing an important role, together with Switzerland, Germany and Italy.

Zone / Country	Europe	Australia	China	India	Mexico	Saudi Arabia	South Korea	Taiwan (China)	Turkey
Quantity (Engines)	2319	3	270	119	20	15	475	811	12

Outside Europe, the biggest fleets are located in Taiwan, South Korea, China and India. Turkey also expressed its interest for high speed trains.

The perspectives of ERTMS

If we intent to sum up the figures gathered at the end of this data collection campaign, we can finally say that the following table is a reasonable snapshot of the actual situation of ETCS worldwide:


	ETCS network short and medium perspective ¹ (km)	ETCS network long term perspective ² (km)	Rolling-stock short and medium perspective (engines)	Rolling-stock long term perspective (engines)
Africa, America, Asia, Australia	10049	610	1725	-
Europe	9776	31359	2319	9240

These aggregated figures can be considered as an expression of the UIC members’ feeling concerning ETCS and show a rapid growth of ETCS, especially in the countries outside Europe.


The following chart shows the ETCS timetable per country and takes into account all mentioned project in the countries. Taking the example of Algeria, it should be read as follows: Algeria will have achieved 426 km of ETCS sections (bottom horizontal axis) by 2010 (top horizontal axis).

¹ Sections in commercial operation + contracted ones.

² Planned sections; some countries transmitted plans until 2030.



We also tried to visualize the possible growth of the ETCS network around the world and we were able to produce the chart below depicting its worldwide evolution by 2025.



The success of ETCS outside Europe is likely to continue: for example in Australia, the improvement of the Melbourne's rail network capacity and safety may be a potential application for ETCS in the coming years. Another example is Morocco which has been already considering the implementation of ETCS for its current fleet and infrastructure. In 2008, the European Union granted "advanced status" to this country. Because the construction of a tunnel between the Cherifian Kingdom and Spain is still being discussed, ETCS can be considered as a potential solution for its Maghribi & Atlantic High Speed links. The latter will therefore be the first high speed line in Africa and Arab world, if completed before the Mecca-Madinah project.

Finally, the following tables recapitulate the per country and per status data gathered this year:

Country	Commercial operation (in km)
Austria	67
Bulgaria	230
China	116
Germany	135
Hungary	217
India	50
Italy	472
Luxembourg	67
Romania	92
Slovakia	64
South Korea	238,6
Spain	985
Switzerland	80
Taiwan (China)	1200
The Netherlands	110

Country	Contracted (in km)
Algeria	426
Austria	394
Belgium	336
Bulgaria	147
China	3780
Croatia	34
France	300
Germany	298
Greece	564
India	196
Italy	313
Luxembourg	214
Mexico	35
Saudi Arabia	2493
South Korea	404,1
Spain	907
Sweden	676
The Netherlands	123
Turkey	1110
United Kingdom	218

Country	Planned (in km)
Austria	651
Belgium	893
Bulgaria	1020
Croatia	804,2
Czech Republic	1332
Denmark	1952
Finland	664
France	4570,5
Germany	2363
Greece	79
Hungary	832
Italy	1569
Lithuania	626
Norway	3797,4
Poland	648,8
Portugal	1040
Romania	715
Slovakia	784
Slovenia	1174
Sweden	2218
Switzerland	2900
Turkey	610
United Kingdom	886

Country	Total ETCS network in km (pilot + commercial operation + contracted + planned; horizon 2030)
Algeria	426
Australia	40,3
Austria	1112
Belgium	1329
Bulgaria	1397
China	3896
Croatia	838,2
Czech Republic	1355,4
Denmark	1952
Finland	664
France	4870,5
Germany	2796
Greece	793
Hungary	1049
India	246
Italy	2354
Lithuania	626
Luxembourg	281
Mexico	35
Norway	3797,4
Poland	648,8
Portugal	1040
Romania	837
Saudi Arabia	2493
Slovakia	884
Slovenia	1257
South Korea	642,7
Spain	1985
Sweden	2894
Switzerland	2980
Taiwan (China)	1200
The Netherlands	233
Turkey	1720
United Kingdom	1104

Some statistics on GSM-R

GSM-R Implementation Status in Europe

Background

For the readers not having seen the 2007 Atlas of the ERTMS Implementation, we would like to remind that GSM-R have been generally deployed on national basis, in many cases replacing the old analogue systems. GSM-R is covering therefore more lines then the ones foreseen for ETCS. In case of ETCS Level 1, GSM-R is assuring the voice traffic, while for ETCS L2 an higher, GSM-R is assuring both voice and data traffic.

Consequently, GSM-R status information is given by the color of the map which is showing different implementation phases at global national level. In the Atlas annex, you can find more detailed maps.

We wish thank the ERIG member's who has supported us in producing this work, as well as to the GSM-R Industry Group, who supported us in some of the outside of Europe cases.

GSM-R Status in Europe, end 2008

GSM-R's deployment has continued since 2007. There are 17 implementers end 2008: Austria, Belgium, Lithuania, Bulgaria, Czechia, Finland, France, Germany, Greece, Italy, Netherlands, Norway, Slovakia, Spain, Switzerland, Sweden, United Kingdom. Denmark, Poland, Portugal, Romania are preparing for tender.

Outside Europe, GSM-R is installed in China, and is under deployment in Algeria, India, Turkey and Saudi Arabia. It is under discussion in Australia.

GSM-R - crossing the borders


In Europe, the International interconnections and the related traffic started to grow.

You can see here, below, the actual existing interconnections, and traffic measured beginning 2009. The values are still small, but we can see a 90 % increase, compared with the average traffic load beginning 2008.

#	Source	Destination	Load_Avg [%]	Load_Max [%]
1	Czech Republic	Germany	0,9	13,7
2	Belgium	Germany	0,9	8,5
3	Germany	Netherlands	4,8	14,3
4	Switzerland	Germany	1,3	7,9
5	France	Germany	1,3	8,4
6	Austria	Germany	2,0	16,5
7	Germany	Sweden	2,6	12,2
8	Italy Milan	Switzerland		
9	Italy Rome	Switzerland		
10	Netherlands	Belgium		11,0
11	Norway	Sweden		
12	France	Switzerland	0,1	23,0
13	Belgium	France	0,1	1,8
14	Austria	Switzerland		
15	France	Italy Rome	0,1	1,5
16	Austria	Czech Republic		
	Italy Rome	Italy Milan		
		Max	4.8	23.0




GSM-R is taken into account in all of Europe, and not only. It is now in tendering/planning phase in all European Countries. Here below, we have represented all countries in their actual implementation status.




In Europe, GSM-R is planned to be deployed for 149210 km; taking into account the networks where such plans are prepared (224135 km of Railways), it means that 66, 57% of the European Railway Network is planned to be covered with GSM-R.

Tabel 1
The GSM-R European Planning



From this, 73.293 km are already constructed (49, 12 % from the planned), and 56.991Km are in operation (38, 5%)!

GSM-R Implementation Status - End 2008



As installed Network Elements,

BTS (Base transceiver Station)	pcs.	9188
BSC (Base Station Controller)	pcs.	146
MSC (Mobile Station Center)	pcs.	33
HLR (Home Location Register)	pcs.	26
IN (Intelligent Node)	pcs.	17
NMC (Network Management Centre)	pcs.	19


On the mobile side, 198.525 mobiles are planned, from which 65.318 are activated (32, 9%) (This refers to Cab Radios, EDOR's (ETCS Only Data Radio), Handhelds – GPH (General Purpose Handheld), OPH (Operational Purpose Handheld), OPS (Operational Purpose for Shunting) and Modems)

From this, 27.943 are activated cab radios, which include also EDOR's.

As for Dispatchers, 5.063 are planned, from which 1.557 are activated, which means 30, 7%.

For 2009, we expect a continuous advance of the implementation, according to plans. Denmark, Portugal, Poland, Hungary and Romania should start/finalize the tenders, and start the implementation. The international traffic is expected to grow, on a more abrupt curve then 2007/2009. The applications using GSM-R will also grow and diversify.

Here below, you can see the implementation roadmap, according to National Implementation Plans:



LIST OF ABBREVIATIONS

ASFA	Anuncio de Señal y Frenado Automático (Spanish CC-system)
ATB	Automatisch Train Beïnvloeding (Dutch CC-system)
ATP	Automatic Train Control System
BACC	Blocco Automatico Correnti Codificate (Italian CC-system)
BSC	Base Station Controller
BTS	Base Station Transceiver Station
CC	Control-Command
Ebicab	CC-system used in Sweden and other countries
ERTMS	European Rail Traffic Management Sytem
ETCS	European Train Control System
ETSI	European Telecommunication Standardization Institute
EU	European Union
Eurocab	ETCS on-board device
EVM	Hungarian CC-system
GIS	Geographical Information system
GPRS	General Packet Radio Service
GSM	Global System Mobile
GSM-R	Global System Mobile – Railway
HLR	Home Location Register
hom. P.	homologation process
IN	Intelligent Node
KVB	Contrôle de Vitesse par Balise (French CC-system)
LS	Czech CC-system
LTM	Loop Transmission Module
LZB	Linienzugbeeinflussung (CC-system used in Germany and other countries)
Memor II+	CC-system used in Luxembourg
MoU	Memorandum of Understanding
MSC	Mobile Switching Centre
NMC	Network Management Centre
PZB	Pünktförmige Zugbeeinflussung (CC-system used in Germany and other countries)
RBC	Radio Block Centre
SCMT	Sistema per il Controllo della Marcia dei Treni (Italian CC-system)
SHP	Samoczynne Hamowanie Pociagu (Polish CC-system)
Signum	Swiss CC-system
STM	Specific Transmission Module
TBL	Transmission Balise Locomotive (Belgian CC-system)
TEN	Trans European Network
t.p.	tender process
TPWS	Train Protection and Warning System (British CC-system)
TSI	Technical Specification for Interoperability
TSI CC&S	TSI for control-command and signaling
TVM	Transmission Voie Machine (CC-system used in France and in other countries)
UIC	Union Internationale des Chemins de fer
UNIFE	Union des Industries Ferroviaires Européennes
UNISIG	Union Industry of Signalling
ZUB	Zugbeeinflussung (CC-system used in Denmark and Switzerland)




ANNEX: detailed GSM-R maps

ANNEX: detailed GSM-R maps

AUSTRIA




GSM-R Ausbauplan




BELGIUM


GSM-R PREVISION D'IMPLEMENTATION DU GSM-R SUR LES LIGNES PRIO 0, 1, 2 ET 3




BULGARIA




CHINA






CZECH REPUBLIC




DENMARK



FINLAND

- = Network implemented by the end of 2006
- = Network implementation in 2007
- = Network implementation in 2008



FRANCE (Tranche 1 – EE-HSL)



DB Netz AG
GSM-R - digitaler Zugfunk



GERMANY




Basic package + additional lines package 1.1
~ 24.000 km + ~ 1000 km

Additional lines package 2
~ 4.000 km


GREECE




HUNGARY






 In service


 In construction

ITALY

NORWAY




POLAND




- **GSM-R – Conventional lines**
- **GSM-R – High Speed lines**
- **Secondary Lines – Public GSM**

PORTUGAL



SLOVENIA






— In service

— In construction

— In project


SPAIN

SWEDEN




Planerad MobiSIR täckning september 2004
Planned MobiSIR coverage September 2004


SWITZERLAND



THE NETHERLANDS



UNITED KINGDOM



ACKNOWLEDGMENTS

Such a document would never have been produced without collaboration between numerous participants. Therefore, the UIC would like to thank all its members throughout the world for providing the data leading to this Atlas, together with the UIC ERIG (European Radio Implementers Group) for GSM-R data, and UNIFE.

For further details you can contact:

UIC - International Union of Railways

Paolo de Cicco (*responsible for co-ordination ERTMS Platform*): decicco@uic.asso.fr

Françoise El Alaoui (*Communications*): elalaoui@uic.asso.fr

Dan Mandoc (*GSM-R data*): mandoc@uic.asso.fr

Khalid Agrou (*ETCS data*): agrou@uic.asso.fr

Florian Lesné (*GIS*): lesne@uic.asso.fr

Marija Petkovski (*Design*): petkovski@uic.asso.fr

Sources

UIC members - ERIG - UNIFE

Printed by
Lienzo Gráfico Impresores
Avda. de Hytasa, 14. Polg. Hytasa.
c/Lienzo, 10. 41006 Sevilla - España
March 2009
Dépôt légal March 2009

ISBN 978-2-7461-1630-6 (English version)



INTERNATIONAL UNION OF RAILWAYS
UNION INTERNATIONALE DES CHEMINS DE FER – INTERNATIONALER EISENBAHNVERBAND
16 rue Jean Rey – F 75015 PARIS
<http://www.uic.asso.fr>